

SPORTSGUARD SANDING & FINISHING GYMNASIUM FLOORING



Granwood



Maplewood



Other

Specifications for the Work Being Proposed:

- 1) The Gymnasium Floor will be cleaned and prepared to receive the Sanding, Sealing and other work outlined in this proposal – Prior to beginning this work.
- 2) The Gymnasium Flooring will be sanded in accordance with standard specifications and requirements to insure that the floor is smooth and monolithic. This work will involve drum-sanding with medium to very light drum-sanding paper. This helps to insure the appropriate monolithic surface.
- 3) The **SEALING** process involves two coats of High-Grade Polyurethane, applied approximately one day apart. The first coat is Buff-Sanded after drying to insure the surface is smoothed to receive the second **SEAL** coat.
- 4) After the second **SEAL** coat is dry, the Gym Floor **LINES** and **LOGO** (As Required) will be **PAINTED**, using the same Gamelines and Logo Layout you now have or some other design - onto your gym floor. Also, only Industrial Grade Sherwin Williams **OSHA, ICI** Paints or equal Paints are used for Gamelines, Logos and Lettering.
- 5) After all Gamelines are dry, the first **FINISH** Coat of High-Grade Polyurethane is applied.
- 6) Following the Drying Process of the First **FINISH** Coat, the Surface Buff-Sanded to insure the Floor Surface is Smoothed to receive the Second **FINISH** coat.

The above outlined process will require approximately **7 – 10** days. You should allow **72** hours Drying Time before using the Gym Floor.

This quotation is based on the Dimensions outlined on the Price Quotation for this Work.

Special Information:

- 1) Sanding, Painting and Finishing the Gym Floor, Please allow **7 – 10** Days.
- 2) You would need to be off the floor **72** hours after the floor is completed.
- 3) State Taxes have not been included.
- 4) Payment will become due when the work is completed.

